


Contrary to popular belief,
beauty is actually 40mm deep.

Colorbond

RUSKO

Premium Tile Roof



40mm



Edge Cap



Edge Cap as Installed



Rollformed Ridge Roll
with Embossment



Ridge Roll
as Installed



Color may vary from actual product





Colorbond
 World-Class Pre-Painted Galvalume55®
RUSKO
 Premium Tile Roof.

GENERAL PRODUCT INFORMATION

<p>BASE METAL TYPE: Cold Rolled Steel: 275 MPa or 40,000 psi</p> <p>SUBSTRATE: GALVALUME 55™; Aluminum-Zinc alloy-coated steel complying with ISO 9364. Also available in GALVABOND™; Lock Forming Quality (PNS 67:2000)</p> <p>PAINT COATING: <u>STANDARD</u> Double oven-baked epoxy primer and high grade polyester finish.</p> <p><u>OPTIONAL</u> Premium Fluorocarbon (PVDF) paint finish on top of corrosion-resistant epoxy primer</p>	<p>SALT SPRAY TEST RATING: Class 1000 hours (passed 1000 hours of continuous exposure as per PNS 201:1990). The only pre-painted tile-effect profile product in the market to have passed class 1000 rating</p> <p>AVAILABLE THICKNESSES: 0.40mm to 0.60mm</p> <p>LENGTH: Longspan</p> <p>WIDTH: Nominal Width = 1095mm Effective Coverage = 990mm</p>	<p>APPLICATION: Roofing</p> <p>STANDARD COLORS: Pacific Blue, Spanish Red, Tile Red and Baguio Green</p> <p>SPECIAL COLORS: MS Red, Mediterranean Peach, Batangas Brown</p> <p>RECOMMENDED FASTENERS: Steel - # 12 - 24 X 85 mm w/ Rubber Washer Wood - #12 - 11 x 85 mm w/ Rubber Washer</p>
--	--	---


RUSKO TILE ACCESSORIES

ROLLFORMED RIDGE ROLL WITH EMBOSSEMENT





THICKNESSES: 0.40, 0.50 & 0.60mm
LENGTH: 2.44mm or longspan

EDGE CAP



AVAILABLE THICKNESS 0.50mm
NO. of Pieces per PANEL 2 pcs.

RECOMMENDED FASTENER LAYOUT



MANUFACTURING PLANTS & SALES OFFICES



Philsteel Tower 140 Amorsolo St., Legaspi Village Makati City. Tel No. 813-8382
Philmetal Email Ad: philmetal_sales@philsteelgroup.com; Fax No. 840-2123